

Seneca Creek Basin ESA

Quince Orchard Valley Park Area

April 13, 2016

AGENDA

Scope of Work
Project Overview
Review of Alternate Routes
Project Activities
Project Schedule
Who to contact



CONSENT DECREE

Settlement between the WSSC, Environmental Protection Agency (EPA), Maryland Department of Environment (MDE), U.S. Department of Justice and several environmental groups.

Scope of Work and Schedule
 Rehabilitate Sewer Pipes and Manholes
 Impacts 1,000 Square Miles
 24 Sewer Basins



SCOPE OF WORK *Quince Orchard Valley Park*

Rehabilitate 47 Year-Old Sewer Pipeline

> 1,509 Linear Feet (0.29 miles) of Sewer Pipe

Reinforce the Interior of the Pipe by Lining and Coating Existing Walls

➢ 5 Sewer Manholes Repaired




PROJECT OVERVIEW

Sewer Repair, Replacement, Rehabilitation (SR3)


Tree/Brush Clearing
 Install Temporary Access Road
 Pipe Lining/Manhole Rehabilitation
 Remove Temporary Access Road

Site Restoration/Tree Plantings





PROJECT OVERVIEW






ACCESS ROUTES COMPARISON

WSSC Sewer Repair, Replacement, and Rehabilitation (SR³) Program

Seneca Creek Task Order 5 - Quince Orchard Valley Park





ACCESS ROUTES COMPARISON

	Suffolk Terrace	Longdraft Road	Sioux Lane
ROAD	2,900 Linear Feet	4,700 Linear Feet	3,300 Linear Feet
ACCESS TO SITE	40 Foot Wide Access	Denied by Pepco	20 Foot Wide Access
TOPOGRAPHY	Accessible Terrain	Too Steep to Accommodate Construction Vehicles	Too Steep to Accommodate Construction Vehicles
STREAM CROSSINGS	1	2	3
WETLAND & WETLAND BUFFER IMPACT	Minimal Impact	Large Impact 6,000 Square Feet	Large Impact 6,000 Square Feet
TREE REMOVAL	Approximately 58+	Large Scale Tree Removal	Large Scale Tree Removal



ACCESS ROUTE COMPARISON

	Suffolk Terrace	Longdraft Road	Sioux Lane
PEPCO RIGHT OF WAY	No Conflicts	 Longitudinal Access Denied Low Hanging Overhead Wires 	 Perpendicular Access Low Hanging Overhead Wires
PEDESTRIAN ACCESS	Maintain Path to Park and Schools	N/A	Pedestrian Traffic Blocked
RATEPAYER FUNDS (Access Road Only)	\$669,346	\$1,002,600	\$703,920



PEPCO RIGHT OF WAY



Topography is too steep and path is not wide enough to accommodate construction vehicles.



PEPCO RIGHT OF WAY



Low hanging overheard wires. Construction vehicles will be unable to pass under the wires.



PEPCO RIGHT OF WAY



> Access would require clearing of more trees.





November 11, 2015

Mr. Jason D. Staley, P. E. Project Manager Washington Suburban Sanitary Commission 14501 Sweitzer Lane, 7th Floor Laurel, MD 20707

> Re: Request for permission by Washington Suburban Sanitary Commission for longitudinal access through a portion of Potomac Electric Power Company's Quince Orchard to Bureau Standards 150 ft wide 69 kV T/L Property's No. M-704 to M-706 to conduct sewer pipe and manhole repair in Gaithersburg Maryland.

Dear Mr. Staley:

In response to your request via email dated October 30, 2015 for longitudinal access through a portion of Potomac Electric Power Company's Quince Orchard to Bureau Standards 150 ft wide 69 kV T/L Property's No. M- 704 to M-706 to conduct sewer pipe and manhole repair in Gaithersburg Maryland.

We have reviewed your request in connection with the referenced project. Enclosed is a copy of our Standard Property Use Requirements. As provided in the document, Pepco does not allow longitudinal occupation of its property. If you have any questions please contact Gustav E. Hamilton at 202-873-3589 or me at 202-872-2147.

Respectfully,

Joseph J. Nice

Supervisor, Real Property



VEHICHLES/EQUIPMENT Access Road



Back Hoe





Rubber Tire Loader



Tri-axle Dump Truck



Tractor Trailer

ACCESS ROAD



20-Feet Wide

Allows
 Construction
 Vehicles Access to
 Project Site

- Approximately 120
 Working Days to
 Build
- 4-Foot Walkway for Pedestrian Access
- Removed upon Project Completion



VEHICHLES/EQUIPMENT *Pipe Cleaning*



Cured In Place Pipe Reefer Truck



Lining Jetting/Vacuum Truck



Boiler Truck



RESTORATION EXAMPLES









PROJECT SCHEDULE

>Expected Start:



- ✓ <u>Start date TBD</u>; pending litigation resolution
- ✓ 14 Day Notice will be Provided to Start of Construction
- ✓ 48 hour notice prior to Lining Pipes

Expected Duration of Project:

- Approximately 10 months (Depending on Weather)
- Vehicle Access Limited to Times Students are not Walking to/from School



KEY CONTACTS



Joshua Roll, WSSC Contract Manager 301.206.7363, ext-7, joshua.roll@wsscwater.com

Brady Payen, Construction Inspector (On-Site)* 240.444.4056, <u>brady.payen@wsscwater.com</u>

Donald Barrett, Customer Advocate, 301.206.7239, <u>donald.barrett@wsscwater.com</u>

UPDATES: https://www.wsscwater.com/qov



Questions



