


NOTES:

1. EXCEPT AS NOTED ABOVE, TEST LEAD WIRES SHALL MEET THE REQUIREMENTS OF DETAIL C/3.0
2. RUN ALL WIRES IN 2" PVC SHC. 40 CONDUIT FROM THE CONNECTION POINT UNTIL THEY REACH THE BOTTOM OF THE TEST STATION ASSEMBLY.

WASHINGTON SUBURBAN SANITARY COMMISSION	APPROVED: <u>8/12/16</u>  Chief Engineer	STANDARD DETAIL TEST STATION WITH REFERENCE CELL	$\frac{C}{4.5}$
--	---	--	-----------------