

Community Meeting

Takoma Park Water and Sewer Rehabilitation Phase 1 (WSSC Contract No BRCRLR5355C12)

Washington Suburban Sanitary Commission

WWW.WSSCWATER.COM

Takoma Park Community Center

7500 Maple Avenue, Takoma Park, MD 20912 9/17/2018, 6:00PM

WSSC Project Team

Bhusan Basnet – Design Project Manager Phone: 301-206-7946, Email: <u>Bhusan.Basnet@wsscwater.com</u>

- Kevin Lethbridge Construction Manager Phone: 301-206-7339, Email: Kevin.Lethbridge@wsscwater.com
- Curtis Pinder Technical Contracts Supervisor Phone: 301-642-7339, Email: <u>Curtis.Pinder@wsscwater.com</u>
- Brandon Stewart Customer Advocate

Phone: 301-642-1712, Email: Brandon.Stewart@wsscwater.com

Project Designer

The Wilson T. Ballard Company



Background

Existing Infrastructure:

- > The existing pipelines have reached the end of their useful life cycle.
 - Installed: 1920's 1930's
 - Current pipe conditions: infiltration, joint offset, disintegration, holes, corrosion, tuberculation, etc...
 - Materials:
 - Sewer terra cotta,
 - Water cast iron

Infiltration







Broken -Disintegrated



Tuberculated





Infrastructure Enhancements

New Water Infrastructure

- > The new water mains are made from zinc coated Ductile iron pipes.
 - Life expectancy of approximately 100 years
 - Enhanced corrosion protection that includes:
 - Zinc coating external, National Sanitation Foundation (NSF) approved
 - V-Bio Enhanced Polyethylene Encasement
- > 3 new Fire Hydrants
- Project Benefits
 - Increase fire flow and protection
 - Designed to meet future demand

Reduced Leaks and Breaks / Enhanced Emergency Support Less Future Operation and Maintenance





Infrastructure Enhancements

New Sewer Infrastructure

- The new sewer mains are Polyvinyl Chloride (PVC) and High Density Polyethylene (HDPE) pipes
 - Non-Corrosive
 - Chemical resistant
 - Flexible and fatigue resistant
 - Less chance of tuberculation
 - Cost effective



New Water and Sewer Infrastructure provide safe and reliable services to the community



Project Overview

Project Scope:

- Front Yard Installation
- New pipelines:
 - Water Mains: 8-inch (0.2 miles)
 - Sewer Mains: 1 ¼ inch, 8-inches, and 12-inch (0.2 miles)
 - House Connections/Service Lines:
 - Water 1 1/2-inch
 - Sewer 4-inch gravity
- Grinder pumps:
 - 1 ¼-inch service lines
 - Mobile Honda generator w/propane power
 - 12-year warranty (grinder pump) service warranty starts after manufacturer warranty ends
 - 3 properties, involves work inside home



Project Map



Proposed Project Schedule

TAKOMA PARK WATER AND SEWER MAIN REPLACEMENTS PHASE 1





Estimated Schedule

Steps	Contract <= \$1.2 Mil.	Contract > \$1.2 Mil. *
Bid Due	October 1, 2018	October 1, 2018
Contract Award	November 12, 2018	Early January, 2019
Construction Start	December 2018	Late January, 2019
Construction Complete	December 2019	January 2020

* Requires Commissioner's approval

**Timelines are estimated and weather permitting



What to Expect:

- Anticipated Work Schedule: 8:00 am 4:00 pm, Monday-Friday
- Construction Activities:
 - Surveying and Utility Mark-Outs
 - Field Reviews and Inspection
 - Open-Cut (trench) method
 - Excavation/Water and Sewer Mains Installation
- Heavy Construction Equipment
- Reliable water/sewer services will be maintained
- Short periods of water service interruptions can be expected:
 - Up to 8-hours (maximum)
 - 24-hour advance notification will be provided



What to Expect:

- No parking on streets within <u>active</u> construction zones
 - 48-hours advanced notification will be provided.
 - 'NO PARKING' signs will be posted.
 - All roads will remain accessible at all times during construction. However, certain activities <u>may require</u> temporary closures and delays
- Access to homes will be maintained at all times.
- Home Access
 - <u>Not</u> required for homes with gravity sewers installation option
 - <u>Required</u> for homes with grinder pump installation option
 - Ensure an adult 18 or older is home to grant WSSC personnel access into your home.
 - All WSSC employees and contractors will display identification at all times.



What to Expect:

- Construction signs (with contact information) will be posted at multiple locations throughout the project area.
- Other utilities such as Gas, Electric, Fiber Optics, Storm Drainage, etc. will not be impacted by construction activities.
- Warranty information will be provided to each homeowner for the work completed on property at the completion of their section.



Tree Removal

What to Expect

- Trees and shrubs will be replaced in adherence to the City of Takoma Park requirements.
- WSSC and City of Takoma Park Urban Foresters will supervise all tree removal, replacement and pruning.
- Locations of the new trees/shrubs will be decided in consultation with the City of Takoma Park and homeowners.

Tree	Removal	Replanting
Public	19	40
Private	9	21
Total	28	61
Shrub	Removal	Replanting
Public	3	6
Private	10	18
Total	13	24

Typical Notification Signage







Typical Trench Outside Paved Area









Typical Trench Within Paved Area









Typical Construction Equipment









Typical Tree Protection Measures

Trunk Protection



SC

Vhere Water Matters

Alturnamat*



* Installation will take place at three locations to protect grounds and trees.

Silt Fence



Tree Protection



Project Summary

- The existing water and sewer mains are at the end of their useful lives.
- WSSC will be installing new water and sewer mains in the front yard and new service connections to the back of the property at the existing service connection.
- WSSC is committed to minimizing service disruptions during construction.
- > WSSC will restore all areas impacted by construction activities.
- Warranty information is provided to each home owner for the work completed on property at the completion of their section.
- WSSC's goal is to provide a safe and reliable water and sewer services to the community.



Thank You!

Questions?

