

STANDARD SPECIFICATIONS  
SECTION 01770  
PROJECT CLEANUP

PART 1 GENERAL

1.1 DESCRIPTION

- A. Section includes requirements for cleanup, restabilization restoration and disposal to maintain a safe and well-kept job site and properly repair disturbed areas.

1.2 CLEANUP

- A. Proceed with construction cleanup as construction progresses.
  - 1. Remove mud, oil, grease, soil, gravel, trash, scrap, debris, and excess materials that are unsightly or may cause accidents to persons or properties.
  - 2. Remove water from floor areas where electrical power tools are to be used, and prevent stains on concrete that will be exposed in finish work.
  - 3. Select and employ cleaning materials and equipment with care to avoid scratching, marring, defacing, staining, or discoloring surfaces cleaned.
- B. Final Cleanup: Perform immediately before written request for final inspection of Contract Work or any portion thereof.
- C. Besides normal "Broom Clean" requirements, clean exposed surfaces as listed.
  - 1. Glass: Wash and polish.
  - 2. Painted Surfaces: Remove marks, stains, fingerprints, and dirt.
  - 3. Exposed Slabs: Wash, scrape, and scrub, using detergent to remove bond breaker, dirt, and discolorations.
  - 4. Asphalt Paving: Remove mud, oil, grease, dirt, and trash and hose down.
  - 5. Aluminum: Clean following manufacturer's recommendations.
  - 6. Other Surfaces: Remove blemishes, leave clean, uniform, and dust-free.
  - 7. Premises and Site: Remove trash, debris, and surplus excavated material.
- D. Leave premises orderly and "Broom Clean."

1.3 RESTORATION AND RESTABILIZATION

- A. Restore and restablize disturbed areas including, but not limited to staging and stockpiling areas, construction strips, access roads, stream crossings, and areas within acquired right of way.

- B. Proceed with final restoration and restabilization following Restoration Schedule on Drawings and requirements in Sections 02315 and 02920, including seeding, sodding, and paving when season allows.
- C. Disassemble and remove all temporary construction facilities, and leave site in orderly and restored condition following Contract Documents.
- D. Preserve public and private signs, markers, guardrails, and fences, and maintain in existing locations and condition unless written permission is obtained for removal and restoration or replacement.
  - 1. Remove conflicting facilities when grading operations begin and store in manner to keep them clean and in existing condition.
  - 2. Restore to original or new locations at Engineer's direction.
  - 3. Repair or replace damaged items when directed, at no cost to the Commission.
- E. Perform restoration of turf areas following Section 02920.
- F. Perform tree protection, repair, and replacement following Section 02230.
- G. Restore gravel surfaces and roadway shoulders to their condition before being disturbed.
  - 1. Do not reuse shoulder material if contaminated by foreign material.
    - a. Replace with new material of same quality and gradation.
  - 2. Materials and Methods of Construction: Follow jurisdictional requirements and applicable permits secured for this Contract.
  - 3. Surface areas adjacent to shoulders, if left unstable by construction, with stabilized gravel or other acceptable stabilizing material.
- H. Restore pavement, curbs, other paved areas, and sidewalks following requirements elsewhere in Contract Documents.

#### 1.4 DISPOSAL OF WASTE AND EXCESS MATERIALS

- A. Dispose of construction waste and excess materials in authorized County disposal area or in area covered by current grading or sediment control permit.
  - 1. See Section 01110.
  - 2. Furnish 3 copies of grading permits to Engineer before use of disposal site.
- B. Remove waste and excess material disposed of in unauthorized area, and restore area to its condition before disturbance, at no cost to the Commission.
- C. Dispose of human waste in special sites designated therefor.

## 1.5 REMOVAL OF REJECTED MATERIAL

- A. Remove material delivered to Contract site, which has been determined by Engineer to be unsuitable or not following Contract Documents, and dispose of in approved area.

## PART 2 PRODUCTS

NOT USED

## PART 3 EXECUTION

NOT USED

## PART 4 MEASUREMENT AND PAYMENT

- 4.1 Providing for and complying with requirements in this Section will not be measured for payment, but cost will be considered incidental to Contract.

**\*\*WSSC\*\***