



NOTES:

1. PRECAST CONCRETE $f'_c=5000$ PSI @ 28 DAYS.
2. REINFORCEMENT SHALL CONFORM TO ASTM C-478.
3. CAST LIFT LUGS ARE REQUIRED FOR 4" AND 6" RINGS.

WASHINGTON
SUBURBAN
SANITARY
COMMISSION

APPROVED:

9/29/16

[Signature]

Chief Engineer

STANDARD DETAIL

24-INCH PRECAST CONCRETE
MANHOLE TRANSITION RING

S
4.21